



OCEANO COMMUNITY SERVICES DISTRICT

CIPs A-3, A-4, & A-7 SANITARY SEWER UPGRADE PROJECT

Bid Addendum # 1

Response to Bidder Questions

9/28/2026

Question: The Lateral Replacement Repair Schedule on Project Plan Sheet C-103 indicates that the required lateral repair for 1323 19th Street is estimated to be 22 to 32 feet from the sewer main. Confirm these distances are correct.

Answer: The estimated repair distances from the sewer main for 1323 19th Street shall be updated to 5 to 15 feet. The existing 6-inch sewer line is approximately 2-5 feet west of the existing vegetated median. Replace the Lateral Replacement Repair Schedule on Sheet C-103 with the schedule below.

LATERAL REPLACEMENT REPAIR SCHEDULE

1	LOCATION	APPROX. REPAIR LENGTH (FT)	APPROX. DEPTH OF LATERAL (FT)	REPAIR DISTANCE FROM SEWER MAIN (FT)	DEFECT NOTES
	1323 19TH STREET	10	5.42	22 TO 32 5 TO 15	ROOT INTRUSION IN LATERAL
	1830 19TH STREET	5	5.84	12	SEWER OFFSET UNDERNEATH GUTTER
	2160 NIPOMO STREET	15	5.50	0 TO 15	BELLY IN SEWER LATERAL